Leon County
Public Works Department
Engineering Services Division
"People Focused. Performance Driven."

Springhill Road Bridge Rehabilitation

Construction Details

Consultant
- Registe Sliger, Inc.

Progress
- Construction comencement in Summer 2020

Cost
- $350,000.00

Project Schedule

Construction during the Summer School Break of 2020

Contact Information

Chris Muehlemann, P.E.
Project Manager
2280 Miccosukee Road
Tallahassee, Fl 32308
Email:
MuehlemannC@leoncountyfl.gov
Phone: (850) 606-1536
Fax: (850) 606-1501

Felton Ard, P.E.
Customer Support Engineer
2280 Miccosukee Road
Tallahassee, Fl 32308
Email: ArdF@leoncountyfl.gov
Phone: (850) 606-1515
Fax: (850) 606-1501

Project Description

This project provides rehabilitative repair to Springhill Road Bridge over Munson Slough to ensure the long-term safety of this facility. This project provide a permanent solution to the deteriorating approaches that have required several emergency repairs in the past. Springhill Road Bridge was built in 1949 using timber piles, concrete bents, steel and a concrete superstructure. The bridge spans Munson Slough at the outfall into Lake Henrietta. Currently, the bridge's timber piles are showing some deterioration. Additionally, Munson Slough experiences extreme fluctuation of stream elevation. This continual fluctuation has caused weakening of the approaches. The substructure and superstructure are in need of repair to maintain longevity.

Proposed Improvements

- Approach repair
- Additional permanent pile installation
- New guardrail system