Leon County
Public Works Department
Engineering Services Division
"People Focused. Performance Driven."

Old Bainbridge Road Safety Improvement, from US 27 to County Line

Design Details

Consultant
- Gresham Smith

Progress
- Bidding Process

Cost
- $230,000.00

Project Schedule

Final Design has been completed.

Construction Engineering Inspection RFP is under development.

Construction Bid will be advertised in the fall of 2019.

Contact Information

S. George Su, P.E.
Project Manager
2280 Miccosukee Road
Tallahassee, Fl 32308
Email: SuShin@leoncountyfl.gov
Phone: (850) 606-1544
Fax: (850) 606-1501

Felton Ard, P.E.
Customer Support Engineer
2280 Miccosukee Road
Tallahassee, Fl 32308
Email: ArdF@leoncountyfl.gov
Phone: (850) 606-1515
Fax: (850) 606-1501

Project Description

The focus of this safety improvements project, funded by FDOT Local Agency Program, is to construct low-cost and effective safety features on and along the roadway to improve safety of the traveling public and adjacent property owners. The improvements must be completed within the existing right-of-way and without major roadway reconstruction, such as adjustment of roadway profile, addition of travel lanes, or full shoulder widening.

Proposed Improvements

This 3.6 miles segment of Old Bainbridge Road is outside the County's Canopy Road Protection Zone. It has narrow travel lanes (approximately 11-ft wide) and numerous curves, including a S-curve near the St. Paul Missionary Baptist Church. The initial recommendations include adding reduced speed ahead and curve warning signs, installing object markers, piping deep ditches at certain curves, shoulder widening on outside of curves, and possible radar feedback speed limit signs.