

Leon County Public Works Department Engineering Services Division

"People Focused. Performance Driven."

Magnolia Drive Major Infrastructure Improvements

Construction Details

Consultant

· Atkins, Inc

Progress

Bidding

Cost

.

Project Schedule

Current: Bidding Project

Future: Construction Contract Approval by Leon County Board

Construction 2024 Q1

Contact Information

Chris Muehlemann, P.E.
Project Manager
Leon County Public Works, 2280
Miccosukee Road, Tallahassee, Fl
32308
Email:

muehlemannc@leoncountyfl.gov

Phone: 8506061536



Project Description

The Project is located in the southeastern section of Leon County on Magnolia Drive between

South Meridian Street and Apalachee Parkway.

Proposed Improvements

S. Meridian Street to Pontiac Drive (Phase I) (COMPLETE)

- Roadway Reconstruction
- 7 Foot Concrete Path on south side of roadway
- Potable Water and Sanitary Sewer System upgrade
- Enclosed stormwater drainage system on south side of roadway
- 3 Foot Landscape Buffer between path and roadway
- Underground Electric and On-street lighting

Pontiac Drive to Diamond Street (Phase II) (CONSTRUCTION TO BEGIN MARCH 2024)

- · Roadway Reconstruction
- 8 Foot Concrete Path on south and east side of roadway
- 8 Foot Concrete Path between Seminole Dr. and Alban Ave.
- · Potable Water and Sanitary Sewer upgrade
- Enclosed stormwater drainage system on south and east side of roadway
- 4 Foot Landscape Buffer between path and roadway
- Underground Electric and On-street lighting

Diamond Street to Apalachee Parkway (Phase III) (UNDER DESIGN)



Leon County Public Works Department Engineering Services Division

"People Focused. Performance Driven."

Magnolia Drive Major Infrastructure Improvements

- Roadway Reconstruction
- 8 Foot Multi Use Trail on west side of roadway
- 6 Foot Concrete Sidewalk between Circle Dr. and Chowkeebin Nene
- Center median refuge island for Magnolia Drive crosswalk at Chowkeebin Nene
- Enclosed stormwater system on west side of roadway
- Underground Electric
- 4 Foot Landscape Buffer between path and roadway

S. Monroe Street to S. Meridian Street (Phase IV) (COMPLETE)

- Roadway Reconstruction
- 8 Foot Concrete Path on south side of roadway
- Potable Water and Sanitary Sewer System upgrade
- · Enclosed stormwater drainage system on south side of roadway
- 4 Foot Landscape Buffer between path and roadway
- Underground Electric